



- NOTES:
- A. CONCRETE TO BE 30MPA COMPRESSIVE STRENGTH AT 28 DAYS WITH 5-8% AIR ENTRAINMENT.
 - B. REINFORCING BAR TO HAVE 75mm COVER ± 20mm.
 - C. 25mm CHAMFER ON ALL EXPOSED EDGES.
 - D. OPSD 3940.150 "DANGER KEEP OUT" INCLUDED.
 - E. GROUTING IS REQUIRED AROUND PIPE AND LIFTING POCKETS.
 - F. ALL DIMENSIONS ARE IN mm UNLESS OTHERWISE SHOWN.

OPSD 804.05 STEEL GRATES AVAILABLE



INTERNATIONAL EROSION CONTROL SYSTEMS INC.

22295 Hoskins Line Phone: 800-821-7462
 Rodney, ON, N0L 2C0 Fax: 866-496-1990

www.iecs.com

PRECAST CONCRETE HEADWALL

CONFORMS TO OPSD 804.030

DRAWN BY:	D. J	CHECKED BY:	L. A
SCALE: N.T.S	DATE: 06/25/14	SHEET 1 OF 1	